



PRI Construction Materials Technologies LLC

6412 Badger Drive
Tampa, FL 33610
813.621.5777
<https://www.pri-group.com/>

Laboratory Test Report

Report for: Coco Li
Zhengzhou Zhongyuan Silande High Technology Co., LTD
No.28 Dongqing West St., Zhengzhou Hi-Tech
Development Zone, Zhengzhou, Henan, P.R. China-450001

Product Name: MF896L

Project No.: PRI-270-02-01

Dates Tested: March 25, 2019 – April 30, 2019

Test Methods: Texas DOT – Departmental Material Specifications: DMS 6310

Results Summary: Compliant: DMS-6310 - Class 8

Purpose: Evaluate the identified liquid sealant for specification properties in accordance with Texas Department of Transportation Departmental Material Specifications – DMS 6310, Joint Sealants and Fillers.

The product is a one-component, self-leveling, silicone sealant for use in pavement structures.

Test Methods: Testing was completed as required in the Texas Department of Transportation Departmental Material Specifications – DMS 6310, Joint Sealants and Fillers in. Test methods assigned or referenced include ASTM C 679: *Standard Test Method for Tack-Free Time of Elastomeric Sealants*, ASTM C 1183: *Standard Test Method for Extrusion Rate of Elastomeric Sealants*, ASTM D 5329: *Standard Test Methods for Sealants and Fillers, Hot-Applied, for Joints and Cracks in Asphaltic and Portland Cement Concrete Pavements*, and TxDOT Designation: TEX-525-C – Test Procedure for Tests for Asphalt and Concrete joint Sealers.

Sampling: The following materials were received by PRI:

<u>Product</u>	<u>Source</u>	<u>Date</u>	<u>Sampling</u>
MF896L	Zhengzhou, China	March 26, 2019	Manufacturer

PRI-070-02-01

The test results, opinions, or interpretations are based on the material supplied by the client. This report is for the exclusive use of stated client. No reproduction or facsimile in any form can be made without the client's permission. This report shall not be reproduced except in full without the written approval of this laboratory. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

Results:

Property	Test Method	Result	Requirement
Physical Property Requirements			
Flow at room temperature 1 specimen; place vertical within 10 sec.; Evaluate after 30 minutes			
Type SL – Slump (mm)	TEX-525-C	NR	--
Extrusion Rate 1 specimen; Cond. sealant 16h @ 73.4±3.6°F & 50±5%RH; Test Cond. @ 73.4±3.6°F & 50±5%RH Test with polyethylene nozzle @ 90psi for 60s	ASTM C 1183 Procedure A modified		
Specific Gravity		NR	--
Extrusion Rate (g/min)		NR	--
Tack-Free Time (min) 1 specimen; Test Cond. 73.4±3.6°F & 50±5%RH; 1oz weight applied to specimen for 5±1 sec	ASTM C 679	60	≤ 120
Nonvolatile Content (%) 5 specimens; 10±0.5g; Expose at 158±2°F for 168±2h	TEX-525-C	97.2	≥ 93
Tensile Strength (psi) 1 specimen per condition; 1/2" x 1/2" x 2"; Substrate – unprimed concrete Cure 6d+2h @ 75±5°F and 55±5%RH; Test 5 cycles; Rate 1/8 in/h Extension 1/2"	TEX-525-C/ ASTM D 5329		
Air-cured		9.3	4-30
Water bath @ 77±1°F		9.2	4-30
Oven @ 158±2°F		9.8	4-30
After bond test		9.6	4-30
24-hr extension test for all specimens [Pass/Fail]		Pass	Pass

Notes: "NR" = Not Required

PRI-070-02-01

The test results, opinions, or interpretations are based on the material supplied by the client. This report is for the exclusive use of stated client. No reproduction or facsimile in any form can be made without the client's permission. This report shall not be reproduced except in full without the written approval of this laboratory. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

Statement of Compliance:

The product tested complies with the required specification properties of Texas Department of Transportation Departmental Material Specifications – DMS 6310, Joint Sealants and Fillers. The laboratory test results presented in this report are representative of the material supplied.

Signed:



Jason Simmons
Director

Date:

April 30, 2019

Report Issue History:

Issue #	Date	Pages	Revision Description (if applicable)
Original	04/30/2019	3	NA

END OF REPORT

PRI-070-02-01

The test results, opinions, or interpretations are based on the material supplied by the client. This report is for the exclusive use of stated client. No reproduction or facsimile in any form can be made without the client's permission. This report shall not be reproduced except in full without the written approval of this laboratory. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.